



FIBRESHIP 2ND PUBLIC WORKSHOP
La Ciotat (France) – 25TH May 2019

OVERALL DESCRIPTION OF FIBRESHIP PROJECT

**ENGINEERING, PRODUCTION AND LIFE CYCLE MANAGEMENT FOR THE COMPLETE CONSTRUCTION OF LARGE
LENGTH FIBRE-BASED SHIPS**

ALFONSO JURADO FUENTES

MSc. Naval architect and marine engineer

Head of R&D department of TSI S.L.

Coordinator of FIBRESHIP Project – H2020 - GRANT NUMBER 736620

alfonso.jurado@tsisl.es

1. MOTIVATIONS OF USING COMPOSITES
2. FIBRESHIP PROJECT DESCRIPTION
3. POTENTIAL BENEFITS IDENTIFIED
4. MAIN OUTCOMES

General view of advantages and disadvantages of using FRP (Fibre-Reinforced Polymers) in marine industry:

Advantages

- High mechanical resistance
- Resistance to corrosion
- Lightness
- Durability
- Flexibility in design and aesthetic aspects
- Dimensional stability
- Dielectric behavior
- Etc.

Disadvantages

- Expensive
- Complex production
- Combustible material
- Restriction from SOLAS in ships over 500 GT (approx. 50m length)
- Etc.

Making the most of
the
ADVANTAGES

+

Trying to overcome
the
DISADVANTAGES



Large-length vessels (>500GT // >50m)


FIBRESHIP
INTEGRAL COMPOSITE SHIP

FIBRESHIP Project


- FIBRESHIP addresses the **feasibility** of using **composite materials** technology for **large-length vessels**, trying to overcome technical challenges and to generate a change in the regulatory framework that will allow the design, building, and operation of this kind of vessels.
- The project consists of:
 - ✓ **analyzing** the possible **impacts** in the **market of this technology**
 - ✓ **evaluating** innovative **composite materials** for marine applications
 - ✓ **developing software tools** capable to assess the structural performance of the vessel and validated through experimental testing
 - ✓ **creating new design guidelines**
 - ✓ **generating new production and monitoring methodologies**

Main particulars of FIBRESHIP Project

- Grant Number: 723360
- Duration: 36 months (2 periods of 18 months)
 - ✓ Start Date: 1st June 2017
 - ✓ End Date: 31st May 2020
- Estimated Project Budget: 11,041,212.50 €
- Requested EU Contribution: 8,866,322.75 €
- TRL: 7-9
- Made up of 18 partners with broad skills and knowledge in different complementary disciplines.



FIBRESHIP PROJECT DESCRIPTION (2/3) – Thematic approach considered



CATEGORY I Light Commercial Vessels




Vessel selected:
Container Vessel

Other options:

- RORO vessel
- Car Carrier vessel
- Multi-purpose vessel
- Freezer vessel
- LNG vessel
-



CATEGORY II Passengers Transportation & Leisure Vessels



Vessel selected:
ROPAX

Other options:

- Ferry
- Passenger vessel
- Megayacht
-



CATEGORY III Special Services Vessels



Vessel selected:
Fishing Research Vessel

Other options:

- Fishing vessel
- Seismic Vessel
- Offshore Supply vessel
- Rescue vessel
-



A

Structural Weight reduction

Fuel Consumption
Reduction

Increase Payload Capacity

Underwater Radiated Noise
(URN) Reduction

Lower Greenhouse Gas
Emissions

Higher Recycling Rate



Reduced Maintenance & Life
Cycle Costs

Immune to Corrosion


Continuous Structural Health
Monitoring

Possibility of Using Wireless
Sensors


Aesthetic Improvements

B

MAIN OUTCOMES (1/3) – Expected Results



Real-scale demonstrator of a Fishing Research Vessel (FRV) module is being built at iXblue facilities in La Ciotat (France).






Fishing Research Vessel (FRV)
of 85m of length



Demonstrator:
Engine room and other above accommodation spaces.
(Approx.: 11m x 11m x 8.6m)

Summary of expected overcome challenges at the end of the project

- Analyzing the potential **impact in the shipping market** of this technology
- **FRP methodology selection** and identification of innovative fiber-based materials
- **Structural design of large-length vessels (>50m)** based on composites according to:
 - ✓ Structural behavior (ULS)
 - ✓ Fatigue behavior (FLS)
 - ✓ Fire behavior
- Development and validation of **numerical software tools** capable to assess the structural performance of the vessel
- **Modular construction** of vessels in composite materials
- Identification of new **structural connections**
- **Adaptation** of the shipyards to the new construction procedures
- Request of **new regulatory frameworks** to allow the use of FRP in large-length ships
- **Structural health monitoring strategy** definition of vessels
- **Life cycle assessment (LCA)** of fibre-based vessels
- Building a ship block as a **demonstrator** of the project advances





Any question?

THANK YOU



www.fibreship.eu

ALFONSO JURADO FUENTES
MSc. Naval architect and marine engineer
Head of R&D department of TSI S.L.
Coordinator of FIBRESHIP Project
alfonso.jurado@tsisl.es

BACK-UP SLIDES

- **Short Term (0 Years)**
- **Medium Term (1/3 Years)**
- **Medium/Long Term (3/5 Years)**

- Classification Societies: Standards and Rules
- Owners: specifications & orders
- Shipyards: facilities adaptation
- Designers: design process

Business Opportunity

- Massive application of FRP-materials
- Enhance competitiveness of the European Operators
- Enhance competitiveness of European shipbuilding industry

Relevant advance over the traditional methods, allowing the exploitation of the new solutions and procedures in the existing market

POLICIES

ENVIRONMENTAL

- Fuel safety / Gas Emissions
Directive 2012/33/EU
- Life cycle performance & reduced maintenance costs
Directive 2013/1257/EU
- Underwater Noise impact
Directive 2008/56/EU

Safety SOLAS / IMO / EMSA

- Structural resistance criteria
- Fire safety
- Stability
- etc...