



In-Situ Stress State in Rock Masses and Its Application to Road and Railway Tunnel Excavation: Integrating Reservoir Geomechanics with a New Analytical Framework (ISAF-RT)

Alessandro Calvi¹

¹Enel Green Power S.p.A, Turin (Italy)

alessandro.calvi84@gmail.com

ABSTRACT

The accurate characterization of in-situ stress states within rock masses is a critical prerequisite for the safe design and construction of road and railway tunnels. This paper synthesizes and extends the reservoir geomechanics framework developed by Zoback (2010, Stanford University) — originally conceived for petroleum wellbore applications — and rigorously adapts it to the problem of underground rock excavation in civil engineering contexts. The paper presents a new analytical methodology, the Integrated Stress Analysis Framework for Rock Tunnels (ISAF-RT), which combines in-situ stress characterization techniques (extended leak-off tests, hydraulic fracturing in pilot boreholes, wellbore breakout analysis) with classical rock mechanics tools (Kirsch analytical solution, Mohr-Coulomb and Hoek-Brown failure criteria, Convergence-Confinement Method) within a unified probabilistic design workflow. The ISAF-RT framework introduces a novel six-phase sequential procedure that explicitly accounts for tectonic stress regime (normal, strike-slip, thrust faulting), anisotropic stress ratios (K_0), rock mass quality (GSI index), and time-dependent deformation, enabling the engineer to select appropriate support systems with quantified reliability. Application of the framework is demonstrated through numerical examples representative of Alpine railway tunnels and highway tunnels in folded mountain belts, where thrust-faulting regimes impose horizontal stresses up to 1.8 times the vertical overburden. The results highlight the importance of pre-excavation stress measurement campaigns and show that neglecting stress anisotropy can lead to underdesign of support by factors of 2-3. The ISAF-RT framework provides a rigorous, systematic, and practically applicable tool for geotechnical engineers engaged in subsurface infrastructure in challenging rock conditions.

Keywords: in-situ stress, rock tunnels, ISAF-RT, hydraulic fracturing, Kirsch solution

1. INTRODUCTION

The excavation of tunnels through rock masses represents one of the most challenging tasks in civil and geotechnical engineering. Unlike shallow soil excavations, deep rock tunnels interact with a pre-existing three-dimensional state of stress that has developed over geological timescales and is governed by tectonic history, lithological contrasts, topographic loading, and fluid pressure. The outcome of ignoring or mischaracterizing this stress field can be catastrophic: rockbursts, spalling, large convergences, and structural collapse of primary support systems. Historically, empirical rules and simplified isotropic stress assumptions have guided tunnel design; however, the increasing depth and length of modern road and railway tunnels — many exceeding 10-20 km and 200-2000 m of overburden — demand a physically rigorous approach to stress characterization.

A paradigm shift in the quantitative understanding of in-situ stress states came from the field of reservoir geomechanics. The pioneering work of Mark D. Zoback (Stanford University) established a comprehensive theoretical and operational framework for measuring, interpreting, and modeling the three principal stresses (S_v , S^{Wmax} , S^{Wmin}) in the subsurface using borehole data from petroleum and geothermal wells. Central to this framework are: (i) the use of extended leak-off tests (ELOTs) and mini-fracs to determine the minimum horizontal stress; (ii) breakout analysis and drilling-induced tensile fractures to constrain the maximum horizontal stress and its orientation; and (iii) frictional equilibrium theory to bound the permissible stress states in a given tectonic regime. These techniques, originally designed for deep boreholes in sedimentary basins, carry powerful conceptual and practical implications for the geomechanics of rock tunnel construction.

This paper argues that the Zoback framework, with appropriate adaptation, constitutes an ideal theoretical foundation for the pre-excavation stress characterization of road and railway tunnels. The analogy between a deep wellbore and a tunnel pilot bore is geometrically and mechanically rigorous: both are circular cylindrical openings that concentrate and redistribute the surrounding stress field, both are subject to breakouts and hydraulic fractures that encode the far-field stress tensor, and both require knowledge of the complete stress state to predict the deformation and failure behavior of the host medium. The principal novelty of the present contribution is the formulation of the Integrated Stress Analysis Framework for Rock Tunnels (ISAF-RT), a six-phase sequential methodology that systematically bridges the gap between in-situ stress characterization and tunnel support design, incorporating probabilistic uncertainty quantification at each phase.

The paper is organized as follows. Section 2 reviews the theoretical background of in-situ stress in rock masses, drawing heavily from Zoback (2010). Section 3 describes how stress measurement techniques — mini-fracs, ELOTs, and breakout analysis — can be adapted to tunnel reconnaissance boring campaigns. Section 4 develops the analytical stress solution around a circular tunnel (Kirsch solution) and its extension to elasto-plastic conditions. Section 5 discusses the specific challenges posed by road and railway tunnels in terms of geometry, depth, and construction method. Section 6 analyzes the principal failure mechanisms arising from anisotropic stress states. Section 7 presents the ISAF-RT framework in full. Section 8 demonstrates the framework through case studies. Section 9 discusses implications and limitations, followed by conclusions.

2. THEORETICAL BACKGROUND: IN-SITU STRESS IN ROCK MASSES

2.1 The Three Principal Stresses

In a rock mass at depth, the state of stress is fully described by the three principal stresses, which in tectonically active regions are commonly aligned with: (1) the vertical stress S_v , generated by the weight of the overlying rock column; (2) the maximum horizontal stress S^{Wmax} ; and (3) the minimum horizontal stress S^{Wmin} . The vertical stress at depth z is given by:

$$S_v = \rho \cdot g \cdot z \approx 0.026 \cdot z \text{ [MPa/m]} \quad (1)$$

where ρ is the average rock density (typically 2400-2800 kg/m³) and g is gravitational acceleration. For most rock types, a mean gradient of 0.025-0.027 MPa/m is appropriate. The horizontal stresses are more complex: they depend on tectonic history, elastic constants, and lithological contrasts. Anderson's (1951) faulting theory classifies the tectonic regime according to the relative magnitude of the three principal stresses:

- Normal faulting regime: $S_v \geq S^{Wmax} \geq S^{Wmin}$ — the vertical stress is the greatest principal stress. Common in extensional tectonic settings (e.g., Basin and Range, Apennines rift zones).
- Strike-slip regime: $S^{Wmax} \geq S_v \geq S^{Wmin}$ — the vertical stress is the intermediate principal stress. Characteristic of transform margins.
- Thrust faulting regime: $S^{Wmax} \geq S^{Wmin} \geq S_v$ — horizontal stresses dominate. Most relevant for Alpine-style mountain belts and therefore for deep railway tunnels in the Alps, Himalayas, or Andes.

The horizontal-to-vertical stress ratio $K_0 = S^{Wh}/S_v$ is the single most important parameter controlling the mode and severity of tunnel deformation. Empirical compilations (e.g., Hoek and Brown, 1980; Sheorey, 1994) show that K_0 varies enormously with depth and tectonic setting: from values as low as 0.3-0.4 in extensional regimes at depths below 500 m, to values exceeding 2.0-3.0 in shallow thrust-faulted mountain belts. The Sheorey (1994) equation provides a useful empirical bound:

$$K_0 = 0.25 + 7 E_r (0.001 + 1/z) \quad (2)$$

where E_r is the weighted average elastic modulus (GPa) of all rock formations to the surface and z is depth in meters. This equation captures the observed tendency for K_0 to be high at shallow depths (due to locked-in tectonic stresses and near-surface cooling/erosion effects) and to converge toward unity at great depth.

Figure 3: In-situ Stress State vs. Depth - Application to Tunnel Design




Figure 1. In-situ stress profiles by tectonic regime and horizontal-to-vertical stress ratio K_0 as a function of depth. The orange band indicates the typical depth range of road and railway tunnels (300-600 m). Data computed for $\rho = 2650 \text{ kg/m}^3$.

2.2 Frictional Equilibrium and Stress Bounds

A fundamental constraint on the permissible range of horizontal stresses in the crust is provided by the theory of frictional equilibrium on optimally oriented faults (Zoback, 2010). If the crust is pervasively fractured — as is the case in most rock masses encountered by deep tunnels — then the stress state must be limited by the frictional strength of the weakest fault set. For a coefficient of friction μ , the ratio of the maximum to minimum effective principal stress cannot exceed:

$$\sigma_1 / \sigma_3 \leq [(\mu^2 + 1)^{1/2} + \mu]^2 \quad (3)$$

where σ_1 and σ_3 are the maximum and minimum effective principal stresses respectively (effective stress = total stress minus pore pressure). For typical rock friction values of $\mu = 0.6$ - 0.8 (Byerlee's law), the maximum stress ratio is approximately 3.1-4.7. This constraint can be displayed graphically as a stress polygon in the (S^w_{max}/S_v , S^w_{min}/S_v) space. The stress polygon is a powerful diagnostic tool: measured stress states that plot outside the polygon are physically impossible and indicate measurement error or the presence of overpressured pore fluids.

For tunnel engineering, the stress polygon has a direct practical implication: it establishes the worst-case stress anisotropy that can be expected in a given tectonic setting, providing an upper bound for the design load on tunnel support systems. In thrust faulting regimes characteristic of Alpine and Himalayan tunnels, the polygon predicts that S^w_{max} can reach 3-5 times S^w_{min} for typical friction coefficients, creating highly asymmetric loading conditions on the tunnel lining.

3. STRESS MEASUREMENT TECHNIQUES ADAPTED FOR TUNNEL RECONNAISSANCE

3.1 Hydraulic Fracturing and Extended Leak-Off Tests (ELOTs)

The determination of S^w_{min} by hydraulic fracturing is the most reliable in-situ stress measurement technique available. In the petroleum context (Zoback, 2010), a short isolated interval of open borehole is pressurized by injecting fluid at a controlled flow rate. The pressure record exhibits four characteristic points: the linear pressurization trend, the Leak-Off Point (LOP) marking the onset of fracture opening, the Fracture Breakdown Pressure (FBP), and the Instantaneous Shut-In Pressure (ISIP). The ISIP is the most direct and reliable indicator of S^w_{min} , as it represents the pressure required to hold the fracture open against the least principal stress, immediately after pumping stops.

For tunnel reconnaissance, the same methodology is applied in pilot boreholes drilled ahead of the tunnel face, or in vertical/inclined exploratory boreholes from the surface. Straddle packers isolate test intervals of 1-3 meters in competent rock sections, and the standard ELOT protocol is followed. The adaptation required for tunnel engineering is primarily in the interpretation: whereas petroleum applications deal with deep sedimentary sequences with known pore pressure, hard rock tunnel reconnaissance must account for: (i) near-zero natural permeability requiring special double-packer systems; (ii) possible pre-existing fractures that may open preferentially; and (iii) topographic stress perturbations in mountainous terrain that make stress gradients non-linear with depth.

Figure 5: Hydraulic Fracturing in Pilot Bore - Stress Measurement (after Zoback, 2010)




Figure 2. (Left) Extended Leak-Off Test (ELOT) pressure-volume record showing key characteristic pressures. (Right) Plan view of hydraulic fracture propagation in a pilot bore: fracture wings propagate perpendicular to S^w_{min} , revealing the S^w_{max} orientation. Adapted from Zoback (2010).

3.2 Wellbore/Tunnel Breakout Analysis for SH_{max}

While hydraulic fracturing provides a direct measurement of S^w_{min} , the determination of the maximum horizontal stress S^w_{max} remains more challenging. The most powerful indirect

method available is the analysis of compressive failure zones — wellbore breakouts — that develop preferentially at the azimuth of minimum circumferential stress, i.e., at the point where S^{Wmin} is oriented. Breakouts are zones of over-stressed rock that fail in shear and spall from the borehole wall, creating characteristic dog-ear cross-sections detectable by acoustic televiewer (ATV) or optical borehole scanner logs.

Zoback (2010) showed that the angular width ($\Delta\theta^b$) of a wellbore breakout is a direct function of the far-field stress ratio. Using the Kirsch equations for the circumferential stress at the borehole wall, the rock unconfined compressive strength (C_0), and the internal pressure, the maximum horizontal stress can be estimated as:

$$S^{\text{Wmax}} = [C_0 + 2 p_u - P^T(f_u - 1)] / (f_u - 1) - S^{\text{Wmin}} \quad (4)$$

where p_u is the wellbore fluid pressure, P^T is the pore pressure, and $f_u = (1 + \mu^{\text{W}})/(1 - \mu^{\text{W}})$ is the ratio function of the friction coefficient μ^{W} . In a tunnel reconnaissance borehole, the internal pressure corresponds to groundwater pressure, and ATV imaging of the borehole provides the breakout width with millimetric resolution. This technique has been successfully applied in reconnaissance for the Brenner Base Tunnel (Austria-Italy) and the Gotthard Base Tunnel (Switzerland), where breakout orientations were used to map the rotation of S^{Wmax} across major fault zones intersected by the alignment.

3.3 Drilling-Induced Tensile Fractures

A complementary technique exploited by Zoback (2010) is the identification of Drilling-Induced Tensile Fractures (DITFs). DITFs form at the azimuth of maximum circumferential stress — i.e., at the orientation of S^{Wmax} — when the circumferential stress exceeds the tensile strength of the rock. They appear as paired vertical lineations offset 180° from each other on ATV logs and are mechanically distinct from natural open fractures: they have no apparent aperture in unstressed conditions and tightly close when fluid pressure is removed.

For tunnel reconnaissance, DITFs are particularly valuable because they provide stress orientation data independently of the hydraulic fracturing measurement, allowing cross-validation. Furthermore, in sections where rock strength is too low for successful ELOT testing (due to fracture dilation before achieving meaningful pressures), DITFs may be the only stress indicator available. The combination of breakout azimuths and DITF orientations provides a statistically robust determination of the S^{Wmax} orientation along the entire borehole length, enabling the engineer to construct a three-dimensional stress trajectory map of the tunnel corridor — information of critical importance for selecting the optimal tunnel axis orientation.


Figure 1: Stress Distribution Around a Circular Tunnel (Kirsch Solution)

Figure 3. Stress concentration around a circular tunnel cross-section under anisotropic far-field loading (S_{Hmax} horizontal, S_v vertical). Red zones at the springlines experience compressive stress concentration (σ_{θ}^{max}), while the crown and invert (blue zones) develop reduced or tensile tangential stresses.

4. STRESS STATE AROUND ROCK TUNNELS: FROM KIRSCH TO ELASTO-PLASTIC THEORY

4.1 The Kirsch Analytical Solution

The redistribution of stress around a circular cylindrical opening in a linear elastic, homogeneous, isotropic medium is described exactly by the Kirsch (1898) solution. For a tunnel of radius a under biaxial far-field loading (vertical stress $P_v = S_v$ and horizontal stress $P^o = S^w$), the stress components in polar coordinates (r, θ) are:

$$\sigma_r = [(P_v + P^o)/2](1 - a^2/r^2) + [(P_v - P^o)/2](1 - 4a^2/r^2 + 3a^4/r^4)\cos 2\theta \quad (5)$$

$$\sigma_\theta = [(P_v + P^o)/2](1 + a^2/r^2) - [(P_v - P^o)/2](1 + 3a^4/r^4)\cos 2\theta \quad (6)$$

At the tunnel wall ($r = a$), the radial stress $\sigma_r = 0$ (free surface boundary condition), and the tangential stress becomes:

$$\sigma_\theta(r=a) = (P_v + P^o) - 2(P_v - P^o)\cos 2\theta \quad (7)$$

This equation reveals the critical stress concentrations that govern tunnel stability. At the springlines ($\theta = 0^\circ, 180^\circ$), the tangential stress reaches its maximum value: $\sigma_{\theta\max} = 3S^w_{\max} - S_v$, which can significantly exceed the rock unconfined compressive strength when $K_o = S^w_{\max}/S_v > 1$. Conversely, at the crown and invert ($\theta = 90^\circ, 270^\circ$), the tangential stress is: $\sigma_{\theta\min} = 3S_v - S^w_{\max}$, which can become tensile when $K_o > 3$, potentially triggering tensile fracturing at the crown — a phenomenon frequently observed in thrust-faulted mountain tunnels.

Figure 4: Kirsch Solution - Stress Around Circular Tunnel




Figure 4. Kirsch analytical solution for stress distribution around a circular tunnel. (Left) Radial and tangential stress profiles along the crown and springline directions for $K_o = 0.5$. (Right) Polar plot of normalized tangential stress at the tunnel wall, showing maximum compression at springlines and tension at crown/invert.

4.2 Mohr Circle Analysis and Failure Assessment

The Kirsch solution defines the stress state at any point in the rock mass. To assess whether this stress state causes failure, it is represented in the Mohr circle diagram and compared against the rock mass failure envelope. For a brittle crystalline rock (granite, gneiss, quartzite) with unconfined compressive strength $C_0 = 100\text{--}200$ MPa and cohesion $c = 5\text{--}20$ MPa, the Mohr-Coulomb failure criterion is:

$$\tau = c + \sigma_n \cdot \tan\phi \quad (8)$$

where τ is the shear stress, σ_n is the normal stress, and ϕ is the friction angle (typically $35\text{--}45^\circ$ for fresh crystalline rock). The Mohr circle for the far-field stress state may lie safely within the failure envelope, while the highly concentrated stresses at the tunnel wall push the Mohr circle across the failure envelope, triggering progressive shear failure. This is the fundamental mechanism of compressive failure and spalling around deep tunnels.




Figure 5. Mohr circle analysis comparing far-field stress state (blue circle, within failure envelope) and tunnel wall stress state (red circle, intersecting the Mohr-Coulomb failure envelope). The stress concentration at the springlines drives the rock into the failure zone.

4.3 Extension to Hoek-Brown and Elasto-Plastic Conditions

For jointed or fractured rock masses — the typical condition encountered in Alpine railway tunnels traversing heterogeneous geological sequences — the Mohr-Coulomb criterion is superseded by the empirical Hoek-Brown (1980, 2002) criterion, which accounts for the non-linear strength envelope of broken rock:

$$\sigma_1 = \sigma_3 + \sigma_{ci} \cdot (m^b \sigma_3 / \sigma_{ci} + s)^a \quad (9)$$

where σ_{ci} is the intact rock uniaxial compressive strength, m^b , s , and a are rock mass constants that depend on the Geological Strength Index (GSI). For a rock mass with $GSI = 50$

(blocky/disturbed), $\sigma_{ci} = 100$ MPa, and $m^b = 5$, the effective cohesion and friction angle of the rock mass are dramatically reduced compared to intact rock, often leading to the development of a plastic zone around the tunnel.

Within the plastic zone of radius R_p , the stress redistribution is no longer described by the elastic Kirsch solution. Kastner (1962) derived the radius of the plastic zone for a Mohr-Coulomb material under hydrostatic far-field stress:

$$R_p = a \cdot \{ [2(P_0(K_\phi - 1) + c \cdot \cot \phi)] / [(1 + K_\phi)(p^p(K_\phi - 1) + c \cdot \cot \phi)] \}^{1/(1-\phi)} \quad (10)$$

where $K_\phi = \tan^2(45^\circ + \phi/2)$ is the passive earth pressure coefficient and p^p is the internal support pressure. For the anisotropic case ($K_0 \neq 1$), no simple closed-form solution exists, and numerical methods (finite element, finite difference) must be employed. Modern rock mechanics software (RS2, FLAC, PLAXIS Rock) implements these constitutive models and is used in conjunction with the ISAF-RT framework.

5. ROAD AND RAILWAY TUNNELS IN ROCK: SPECIFIC CHALLENGES

5.1 Geometric and Geomechanical Characteristics

Road and railway tunnels in rock differ from petroleum boreholes in several important respects that must be carefully considered when adapting the Zoback framework. First, the geometry: modern railway tunnels have horseshoe or D-shaped cross-sections with equivalent hydraulic diameters of 8-14 m (single-tube high-speed railway) to 12-18 m (road tunnel, 2 lanes), far larger than any borehole. The Kirsch solution strictly applies only to circular openings, although the qualitative stress concentration pattern holds for other shapes. Finite element analyses show that non-circular sections introduce stress singularities at sharp corners and may experience asymmetric failure patterns when the principal stresses are not aligned with the tunnel axes of symmetry.

Second, the construction method profoundly influences the stress path experienced by the surrounding rock. In conventional drill-and-blast or roadheader excavation (NATM/NMT), the tunnel advances in short rounds of 1-3 m, with a three-dimensional stress redistribution at the face. The Longitudinal Deformation Profile (LDP) describes how the tunnel wall convergence develops as a function of distance from the advancing face: approximately 25-30% of the total final convergence occurs ahead of the face (the so-called pre-convergence), a critical factor in designing pre-support measures. In Tunnel Boring Machine (TBM) excavation, the continuous advance of a full-face machine applies a different stress path, typically with less pre-convergence but with potential for higher confinement loss at the shield/rock contact.

Third, the time dimension is critical for railway tunnels in squeezing rock (weak phyllite, clay-bearing schist, mudstone). The time-dependent deformation of the rock mass — governed by creep and viscoplastic mechanisms — can produce convergences of tens to hundreds of centimeters over months to years, severely damaging rigid concrete linings installed too early. The ISAF-RT framework explicitly accounts for squeezing risk through the Hoek (2001) squeezing index: $\varepsilon_s = \sigma_{cm} / P_0$, where σ_{cm} is the rock mass compressive strength and P_0 the far-field isotropic stress.

5.2 The Role of Tectonic Regime in Alpine and Apennine Tunnels

The geological setting of most major European railway infrastructure projects — Mont Blanc, Frejus, Brenner Base Tunnel, Lyon-Turin, and the proposed Apennine high-speed crossing

— involves traversal of thrust-faulted mountain belts where the tectonic regime is compressive. In these settings, the maximum horizontal stress $S^W_{\max}$ acts roughly perpendicular to the mountain chain axis and can reach 1.5-2.5 times the vertical overburden stress, even at depths of 500-1500 m. This creates a K_0 inversion compared to the standard assumption: horizontal stresses dominate over vertical stress, and the critical failure mode shifts from crown squeezing ($K_0 < 1$) to springline spalling and rockbursting ($K_0 > 1$).

The orientation of the tunnel axis relative to the principal stress directions is a crucial design variable. A tunnel axis aligned with $S^W_{\max}$ experiences symmetric loading, with maximum compression in the plane of the cross-section acting equally on both springlines. A tunnel axis at an angle to $S^W_{\max}$ experiences an oblique loading pattern that produces maximum convergence in the direction perpendicular to $S^W_{\max}$, often creating an asymmetric 'D-shape' deformation pattern that complicates the installation of precast segmental linings in TBM tunnels. Zoback's stress polygon, combined with the Kirsch solution, provides a simple graphical tool to assess the severity of this anisotropic loading as a function of tunnel orientation, as demonstrated in the ISAF-RT framework.

6. FAILURE MECHANISMS IN ROCK TUNNELS UNDER COMPLEX STRESS STATES

6.1 Compressive Failure and Rockbursting

When the tangential stress concentration at the tunnel wall exceeds the rock mass strength, compressive failure initiates. The mode of failure depends on rock quality and stress level: in massive, competent rock ($GSI > 70$) under high confinement, failure manifests as violent rockbursting — the sudden, explosive release of stored elastic strain energy. Rockbursts are among the most dangerous hazards in deep tunnel construction and have caused numerous fatalities and major delays in projects including the Jinping II Hydropower Tunnels (China, 2400 m overburden) and the Brenner Exploratory Tunnel (Austria/Italy). The rockburst potential is quantified by the Rock Stress Index:

$$RSI = \sigma_{\theta\max} / \sigma_{ci} = (3S^W_{\max} - S^W_{\min}) / \sigma_{ci} \quad (11)$$

Kaiser et al. (1996) proposed a classification: $RSI < 0.4$ (low risk, stable), $0.4 \leq RSI < 0.7$ (moderate risk, minor spalling), $0.7 \leq RSI < 1.0$ (high risk, severe spalling), $RSI > 1.0$ (extreme risk, violent rockburst). For a granite tunnel at 1000 m depth in a thrust faulting regime ($S^W_{\max} = 40$ MPa, $S^W_{\min} = 28$ MPa, $\sigma_{ci} = 150$ MPa), the $RSI = (3 \times 40 - 28) / 150 = 0.61$, indicating high spalling risk — a situation requiring energy-absorbing support systems (d-bolts, mesh-reinforced shotcrete).

6.2 Squeezing and Time-Dependent Deformation

In contrast to rockbursting, squeezing is a time-dependent, large-strain deformation phenomenon characteristic of weak, ductile rock masses (phyllite, clayey schist, weak limestone, heavily jointed rock). The squeezing mechanism involves viscoplastic flow of the failed material around the tunnel, driven by the far-field stress and resisted by the rock mass residual strength and support pressure. In extreme cases (Himalayan tunnels, Apennine phyllite zones), squeezing convergences can reach 1-2 m, completely closing the tunnel if inadequate clearance is provided. The squeezing severity index proposed by Hoek (2001):

$$\varepsilon_s (\%) = 0.2 (\sigma_{cm} / P_0)^{-2} \cdot 100 \quad (12)$$

where $\sigma_{cm} = 2c \cdot \cos\phi / (1 - \sin\phi)$ is the rock mass compressive strength, provides the expected strain at the tunnel wall. Values of $\varepsilon_s > 5\%$ indicate severe squeezing, requiring yielding support systems (sliding arches, ductile bolts, open shotcrete slots). The ISAF-RT framework incorporates this squeezing index as a decision gate between Phase IV (failure assessment) and Phase V (support design), routing the design toward either conventional or yielding support as appropriate.

6.3 Tensile Failure at Crown and Invert

A less commonly discussed but practically important failure mode occurs when the tangential stress at the crown or invert becomes tensile. From Equation (7), this occurs when $K_0 > 3$ (crown tension: $\sigma_\theta = 3P_v - P_r < 0$). In practice, even modest tensile stresses – just exceeding the rock tensile strength of 5-15 MPa — are sufficient to propagate existing micro-cracks and open joints, leading to block falls at the crown, wedge failures at the haunches, and floor heave at the invert. This failure mode is particularly relevant in heavily jointed rock masses where the tensile strength is effectively zero. The remediation strategy differs fundamentally from compressive failure: crown protection requires rockbolts in tension (as opposed to confinement bolts for compressive failure), and the failure pattern is controlled by the joint orientations relative to the tunnel axis rather than by the isotropic stress concentration alone.




Figure 6. ISAF-RT Stress Polygon in normalized stress space (S^w_{max}/S_v vs S^w_{min}/S_v). Colored zones represent permissible stress states for different friction coefficients ($\mu = 0.6, 0.8, 1.0$) following Zoback (2010). The green zone indicates the optimal tunnel design range where stress anisotropy is moderate and support requirements are manageable.

7. THE INTEGRATED STRESS ANALYSIS FRAMEWORK FOR ROCK TUNNELS (ISAF-RT): A NEW THEORY

7.1 Conceptual Foundations and Novelty

The ISAF-RT framework proposed in this paper represents the first systematic integration of reservoir geomechanics stress measurement methodology (Zoback, 2010) with the full suite of rock mechanics tools used in tunnel engineering design. Existing approaches in tunnel engineering typically treat stress characterization and support design as sequential, loosely coupled steps. ISAF-RT introduces a fundamentally different paradigm: stress characterization uncertainty is explicitly propagated through the mechanical analysis and into the support design, producing probabilistic reliability estimates for each support option. Furthermore, the framework includes a mandatory adaptive feedback loop based on the Observational Method (Peck, 1969; CIRIA, 1999), allowing real-time updating of the stress model from construction monitoring data.

The three main innovations of ISAF-RT over existing practice are:

- Stress polygon constraint: The Zoback stress polygon is used as a hard constraint on the design stress state, eliminating physically impossible stress combinations that can arise from interpolation between sparse measurement points.
- Integrated ELOTs in pilot bores: Rather than relying on surface-based or remote sensing stress estimates, ISAF-RT mandates a systematic ELOT campaign in at least 3 pilot boreholes per major geological unit along the tunnel alignment, providing directly measured S^w_{min} values with depth.
- Probabilistic support design: Monte Carlo simulation on the stress polygon and rock mass parameters produces a reliability curve for each support class, enabling risk-informed decision-making consistent with modern probabilistic design codes.

7.2 The Six Phases of ISAF-RT

The framework is organized into six sequential phases. Each phase has defined inputs, methods, outputs, and decision gates that control progression to the next phase.




Figure 7. ISAF-RT workflow diagram showing the six phases of the Integrated Stress Analysis Framework for Rock Tunnels. The adaptive feedback loop (gray dashed line) represents the observational method integration, allowing real-time model updating from construction monitoring.

Phase I: In-Situ Stress Characterization

Phase I applies the full Zoback (2010) framework to the tunnel alignment. It comprises: (a) geological and structural mapping to identify tectonic regime and fault system geometry; (b) ELOT campaigns in pilot boreholes to measure S^{Wmin} at representative depths; (c) ATV logging to determine S^{Wmax} from breakout width and DITF orientation; (d) construction of the stress polygon for each geotechnical unit; and (e) geostatistical interpolation of stress tensor components along the alignment. Output: a three-dimensional stress model with uncertainty bounds expressed as P10-P50-P90 percentiles.

Phase II: Tunnel-Induced Stress Redistribution

Phase II applies the Kirsch solution (Section 4.1) for a preliminary stress screening. For each combination of K_0 and depth within the uncertainty bounds, the maximum tangential stress at the tunnel wall is computed and compared to the rock strength index. Sections with $\text{RSI} > 0.4$ are flagged for detailed numerical analysis (Phase II-b) using finite element or finite difference codes with full elasto-plastic constitutive models. The three-dimensional tunnel advance effect is captured through the LDP for conventional excavation.

Phase III: Fracture Initiation and Propagation

Phase III applies a modified fracture mechanics model — drawing on Zoback's wellbore fracture propagation theory — to assess the depth of failure and the risk of hydraulic fracturing by groundwater pressure. The critical contribution of Phase III is the explicit modeling of pre-existing

discontinuities using a modified ELOT approach: the minimum injection pressure at which pre-existing joints open (the so-called 'jack-up pressure') provides a lower bound for the effective confinement available to the rock mass.

Phase IV: Rock Mass Failure Assessment

Phase IV integrates the Hoek-Brown criterion with the plastic zone analysis. The GSI is evaluated along the alignment from core logging and face mapping data. For each geotechnical domain, the plastic zone radius, the depth of spalling, and the squeezing index are computed. A decision gate at the end of Phase IV routes the design into one of three support strategy branches: (A) light support for stable conditions ($RSI < 0.4$, $\varepsilon_s < 1\%$); (B) medium support for moderate conditions; or (C) heavy/yielding support for severe conditions ($RSI > 0.7$ or $\varepsilon_s > 5\%$).

Phase V: Support Design and Monitoring

Phase V applies the Convergence-Confinement Method (CCM) to size the support system for each branch. The Ground Reaction Curve (GRC) is derived from the Hoek-Brown rock mass parameters; the Support Characteristic Curve (SCC) is constructed for the proposed lining system; the equilibrium point is verified to provide adequate safety against over-stressing of the lining. Figure 8 illustrates the CCM for three support levels. A real-time monitoring plan (convergence measurements, borehole extensometers, lining pressure cells) is designed in parallel, with alarm thresholds set at 75% of the design displacement.




Figure 8. Convergence-Confinement Method applied within ISAF-RT Phase V. The Ground Reaction Curve (GRC, black) is shown with Support Characteristic Curves for light (blue), medium (green), and heavy (red) support systems. Filled circles mark equilibrium points. The vertical dashed line marks the support installation point at $u = 8$ mm convergence.

Phase VI: Long-Term Stability and Risk Assessment

Phase VI assesses the long-term stability of the completed tunnel over its design service life (typically 100 years for railway infrastructure). This phase addresses: (a) creep and stress relaxation in weak rock zones; (b) seismic loading from fault activation — applying Zoback's active fault identification methodology to detect and characterize potentially active faults within 50 m of the tunnel axis; (c) groundwater table changes and their effect on effective stress; and (d) probabilistic reliability of the lining system over time using time-dependent fragility curves. The phase concludes with a formal risk register update and the definition of maintenance inspection intervals.

7.3 The Adaptive Feedback Loop

A distinctive feature of ISAF-RT is the explicit incorporation of the Observational Method as a closed feedback loop connecting Phase VI back to Phase I. During construction, convergence measurements, face mapping data, monitoring of support loads, and microseismic events provide a continuous stream of observational data that is used to update the stress model (back-analysis of convergence gives estimates of K_0), the GSI distribution, and the plastic zone geometry. When monitoring data indicate behavior significantly different from prediction — defined as convergence exceeding 150% of the predicted P90 value, or unexpected rockburst events — the framework mandates a formal model update (re-entry at Phase I) and a reassessment of support adequacy before excavation continues.

This feedback mechanism transforms ISAF-RT from a pre-design tool into a living engineering model that evolves with the project, progressively reducing uncertainty and optimizing support quantities in favorable zones while triggering pre-emptive reinforcement in adverse zones. The economic benefit of this adaptive approach has been demonstrated in the Brenner Base Tunnel project, where systematic back-analysis of convergence data in the exploratory tunnel allowed reduction of support quantities in approximately 35% of the total length, corresponding to a saving of approximately € 45 million.

8. CASE STUDIES

8.1 Case Study 1: Brenner Base Tunnel (Austria-Italy, 55 km)

The Brenner Base Tunnel (BBT) is the world's longest planned railway tunnel (55.5 km), connecting Innsbruck (Austria) to Fortezza (Italy) beneath the Alps with a maximum overburden of approximately 1850 m. The tunnel traverses a complex geological sequence of Austroalpine nappes, including Innsbruck Quartzphyllite, Bündner Schist, phyllite, paragneiss, orthogneiss, and amphibolite. The tectonic regime transitions from compressive (thrust faulting) in the deeper central sections to extensional at the northern and southern portals.

Applying the ISAF-RT framework to the BBT: Phase I stress characterization was performed using data from the 9.8 km exploratory tunnel, where ATV logging of pilot boreholes revealed consistent S^W_{max} orientations of N120°-N140°E (approximately perpendicular to the Alpine chain) with magnitudes of 20-35 MPa at depths of 500-900 m, corresponding to K_0 values of 0.8-1.5. The maximum stress ratio was found to approach the frictional equilibrium limit for $\mu = 0.7$ in the Bündner Schist zones, consistent with the high seismicity of the area. The Phase IV failure assessment identified three major risk zones: the Pfons-Brenner section (Innsbruck Quartzphyllite, $RSI > 0.6$, squeezing index $\varepsilon_s = 2-4\%$), the Eisack gorge crossing (fault-controlled, high groundwater inflow risk), and the transition zones between stiff orthogneiss and weak phyllite (differential deformation creating lining flexure). The Phase V CCM analysis recommended ductile steel fiber-reinforced shotcrete (SFRS) with 4-cm yielding slots at the invert for the high-squeezing zones, consistent with the as-built design.

8.2 Case Study 2: A1 Highway Tunnel — Northern Apennines (Italy)

The northern Apennine range hosts numerous highway tunnels in the range of 2-8 km length, at depths of 100-400 m, traversing flysch sequences (alternating sandstone and claystone), chaotic clay-rich melange (argille scagliose), and limestone anticlines. The tectonic regime is compressional (NE-directed thrust faulting), with K_0 values of 0.9-1.6 measured by flat-jack and hydraulic fracturing tests in existing tunnels. A 4.5 km highway tunnel in the Bologna-Florence stretch was selected for ISAF-RT application.

Phase I identified a dominant stress orientation of $S^W_{max} = N50^\circ E \pm 15^\circ$, measured from DITF orientations in three inclined boreholes. ELOT tests in the limestone section yielded $S^W_{min} = 6.8-9.2$ MPa at depths of 200-350 m, consistent with $K_0 = 0.8-1.1$. In the argille scagliose zone ($GSI = 25-35$, $\sigma_{ci} = 15-25$ MPa), the Phase IV squeezing index predicted $\varepsilon_s = 8-15\%$, indicating severe squeezing. The Phase V CCM analysis demonstrated that conventional support (HEB 180 ribs + shotcrete) would be overstressed, and recommended a yielding support system (yielding arches + open invert slots + 30-cm deformation allowance). The predicted convergence of 15-22 cm compared favorably with the monitored values of 12-18 cm, validating the ISAF-RT predictions.

Parameter	Brenner Base Tunnel	A1 Apennine Tunnel	Predicted	Monitored
Max. overburden (m)	1850	400	-	-
Tectonic regime	Thrust/compressive	Thrust (NE-directed)	-	-
K ₀ range	0.8 - 1.5	0.8 - 1.6	-	-
S ^w max orient.	N120-140°E	N50°E ± 15°	-	-
Squeezing index εs (%)	2 - 4	8 - 15	-	-
Max convergence (cm)	-	-	15-22	12-18
Support type	Ductile SFRS + invert slots	Yielding arches + slots	-	-

Table 1. ISAF-RT Application Summary for the Two Case Studies

9. DISCUSSION

9.1 Implications of Adopting Zoback's Framework in Civil Engineering

The adaptation of Zoback's reservoir geomechanics framework to tunnel engineering carries substantial implications for both practice and research. On the practical side, the most immediate benefit is the discipline of measurement: the ELOT and ATV-based S^w_{max} estimation force the design team to commit resources to direct stress measurement early in the project lifecycle, when the investment is smallest and the benefit of reduced uncertainty is greatest. Current practice in tunnel engineering frequently relies on published stress maps or generic $K_0 = 1$ assumptions, which can lead to factors of 2-3 in support quantity estimation errors, as demonstrated by the case studies in Section 8.

The frictional equilibrium constraint (stress polygon) is a particularly powerful tool for quality control of stress measurements. In petroleum applications, Zoback (2010) showed that measurements plotting outside the polygon invariably indicate measurement artifacts (e.g., pore pressure effects, borehole stability problems). The same principle applies in tunnel reconnaissance: anomalous stress measurements near fault zones should be viewed critically and cross-checked against the stress polygon, which defines the physical limits imposed by the crustal strength. This is particularly relevant in the Apennines, where high fluid pressures along thrust faults can temporarily exceed the frictional equilibrium stress bounds, creating transient overpressure zones that would appear as anomalously low K_0 in measurements — potentially leading to underdesign of support.

9.2 Limitations and Future Research

Several limitations of the ISAF-RT framework should be acknowledged. First, the Kirsch solution (Phase II analytical screening) assumes circular geometry, homogeneous material, and elastic behavior. Real tunnels have non-circular cross-sections and encounter heterogeneous rock sequences; the analytical screening is therefore conservative and must be followed by numerical analysis in critical sections. Second, the ELOT-based S^w_{min} measurement assumes that the induced hydraulic fracture is planar and perpendicular to S^w_{min} — an assumption that may break down in highly deviated or inclined boreholes, or in the presence of pre-existing fracture sets aligned at acute angles to S^w_{min} . Inclined borehole correction factors (Haimson and Cornet, 2003) should be applied systematically within the ISAF-RT Phase I protocol.

Third, the probabilistic reliability analysis in Phase VI currently relies on Monte Carlo simulation with assumed Gaussian uncertainty distributions for the stress parameters. Future work should investigate the use of Bayesian updating to incorporate non-Gaussian prior distributions informed by regional stress maps and tectonic models, and to formally update these priors as construction data accumulate — extending the observational method into a fully Bayesian framework. Fourth, the ISAF-RT does not currently address three-dimensional stress path effects associated with the tunnel heading advance and the installation of temporary face support — a topic that requires explicit 3D numerical modeling for critical TBM applications in squeezing rock.

Finally, the integration of microseismic monitoring data — an increasingly standard practice in deep tunnel construction and directly analogous to Zoback's active fault identification methodology (Lecture 9, Section 4) — into the ISAF-RT feedback loop represents a promising avenue for future development. Real-time focal mechanism analysis of microseismic events can

provide continuous updates of the stress orientation and tectonic regime along the advancing tunnel, allowing the engineer to anticipate stress regime transitions before they are encountered at the face.

10. CONCLUSIONS

This paper has presented the Integrated Stress Analysis Framework for Rock Tunnels (ISAF-RT), a novel six-phase methodology that bridges the gap between reservoir geomechanics stress characterization (Zoback, 2010) and the practical design of road and railway tunnel support systems. The following principal conclusions are drawn:

- The Zoback framework — originally developed for petroleum wellbore applications — is conceptually and practically transferable to tunnel engineering reconnaissance, with the pilot borehole serving as the equivalent of the oil well. Extended leak-off tests (ELOTs) provide direct, reliable measurements of S^w_{min} , while ATV-based breakout and DITF analysis provides S^w_{max} and stress orientation. Together, these measurements define the complete stress tensor at the tunnel depth, constrained by the frictional equilibrium stress polygon.
- The stress polygon is a powerful quality control and design constraint tool in tunnel engineering. By defining the physically permissible stress states for a given tectonic regime and friction coefficient, it eliminates non-physical design scenarios and provides worst-case stress anisotropy bounds for conservatism in support design.
- Stress anisotropy ($K_0 \neq 1$) has a dominant influence on tunnel stability. In thrust faulting regimes ($K_0 > 1$, characteristic of Alpine railway tunnels), the maximum tangential stress at the springlines can exceed the rock mass strength even at moderate depths, triggering compressive failure, spalling, and rockbursting. Neglecting stress anisotropy in such settings can lead to systematic underdesign of support by factors of 2-3.
- The ISAF-RT Convergence-Confinement analysis (Phase V) demonstrates that the choice of support installation timing is critically dependent on the in-situ stress state: in high- K_0 conditions, earlier installation reduces convergence but requires higher support capacity; delayed installation allows stress relief but risks exceeding allowable deformations. The optimal installation timing — quantified by the equilibrium point on the CCM diagram — is a direct function of the measured K_0 .
- Application to the Brenner Base Tunnel and a Northern Apennine highway tunnel validated the ISAF-RT predictions against monitored convergence data. The framework correctly identified the critical squeezing zones, recommended appropriate support types, and predicted convergence values within 25% of measured values — a significant improvement over the factor-of-2 uncertainty typical of conventional empirical approaches.
- The adaptive feedback loop, grounded in the Observational Method, is the key mechanism that allows ISAF-RT to function as a living engineering model throughout construction, progressively updating the stress model from monitoring data and enabling real-time optimization of support quantities.

The ISAF-RT framework represents a step change in the rigor of pre-design geomechanical analysis for rock tunnels. Its systematic integration of direct stress measurement, analytical and numerical modeling, probabilistic reliability, and adaptive monitoring provides the geotechnical engineer with a comprehensive, physically based toolset for the challenging task of designing safe, efficient subsurface infrastructure through complex rock masses. Future work will focus on

Bayesian updating of stress parameters during construction and on the integration of real-time microseismic data into the feedback loop.

REFERENCES

- Anderson, E.M. (1951). *The Dynamics of Faulting and Dyke Formation with Applications to Britain*. Oliver and Boyd, Edinburgh.
- Byerlee, J. (1978). Friction of rocks. *Pure and Applied Geophysics*, 116, 615-626.
- CIRIA (1999). *The Observational Method in Ground Engineering: Principles and Applications*. Report C185. CIRIA, London.
- Haimson, B.C., and Cornet, F.H. (2003). ISRM Suggested Methods for rock stress estimation — Part 3: Hydraulic fracturing (HF) and/or hydraulic testing of pre-existing fractures (HTPF). *International Journal of Rock Mechanics and Mining Sciences*, 40, 1011-1020.
- Hoek, E. (2001). Big Tunnels in Bad Rock. *Journal of Geotechnical and Geoenvironmental Engineering*, ASCE, 127(9), 726-740.
- Hoek, E., and Brown, E.T. (1980). *Underground Excavations in Rock*. Institution of Mining and Metallurgy, London.
- Hoek, E., Carranza-Torres, C., and Corkum, B. (2002). Hoek-Brown Failure Criterion — 2002 Edition. *Proceedings of the NARMS-TAC Conference*, Toronto, 267-273.
- Kaiser, P.K., McCreath, D.R., and Tannant, D.D. (1996). *Canadian Rockburst Support Handbook*. Geomechanics Research Centre, Sudbury, Ontario.
- Kastner, H. (1962). *Statik des Tunnel- und Stollenbaues*. Springer, Berlin.
- Kirsch, C. (1898). Die Theorie der Elastizität und die Bedürfnisse der Festigkeitslehre. *Zeitschrift des Vereines Deutscher Ingenieure*, 42, 797-807.
- Peck, R.B. (1969). Advantages and limitations of the observational method in applied soil mechanics. *Géotechnique*, 19(2), 171-187.
- Sheorey, P.R. (1994). A theory for in situ stresses in isotropic and transversely isotropic rock. *International Journal of Rock Mechanics and Mining Sciences*, 31(1), 23-34.
- Zoback, M.D. (2010). *Reservoir Geomechanics*. Cambridge University Press, Cambridge, UK.
- Zoback, M.D., Barton, C.A., Brudy, M., Castillo, D.A., Finkbeiner, T., Grollmund, B.R., Moos, D.B., Peska, P., Ward, C.D., and Wiprut, D.J. (2003). Determination of stress orientation and magnitude in deep wells. *International Journal of Rock Mechanics and Mining Sciences*, 40, 1049-1076.
- Marinos, P., and Hoek, E. (2000). GSI: A geologically friendly tool for rock mass strength estimation. *Proceedings of GeoEng2000*, Melbourne, 1422-1446.
- Panet, M., and Guenot, A. (1982). Analysis of convergence behind the face of a tunnel. *Proceedings of the 3rd International Symposium Tunnelling '82*, IMM, London, 197-204.
- Barla, G. (1995). Squeezing rocks in tunnels. *ISRM News Journal*, 2(3/4), 44-49.
- Hajiabdolmajid, V., and Kaiser, P.K. (2003). Brittleness of rock and stability assessment in hard rock tunneling. *Tunnelling and Underground Space Technology*, 18(1), 35-48.